



# CO-OPERATIVE ACADEMY OF PROFESSIONAL EDUCATION

(Established by the Government of Kerala)

College of Engineering Muttathara Campus,  
Vallakkadavu P O, Thiruvananthapuram, Kerala 695 008.

W/55/2021/CAPE

Dated: 02.11.2021

Name of work: Construction of Head office building to CAPE at Muttathara – 2 - Providing partitions & cubicles to the toilet, using laminated sections

### **Specifications & Terms**

Providing partitions & cubicles to the toilet, using laminated sections as per the given specifications including cost of all materials, transportation charges, loading & unloading, shifting to required site, installation charges and all charges but excluding GST. GST to be shown separately and clear.

Specifications for partitions and cubicles

#### **1. General specifications**

- 1.1. Size of Cubicles: As per Drawing
- 1.2. Color of HPL Boards: As Per approved Shade Cards with Suede Finish
- 1.3. Thickness of Compact Laminate: 12mm
- 1.4. Door size: 600mm\*1785mm
- 1.5. Divider Height: 1820mm
- 1.6. Overall height: 1995mm (Including 150mm Ground Clearance)

#### **2. Accessories specifications: Stainless Steel (Grade-316) & Aluminium**

- 2.1. SS Gravity hinges
- 2.2. SS Adjustable leg
- 2.3. SS Coat hook
- 2.4. SS Door knob
- 2.5. Aluminium U channel
- 2.6. SS Lockset with indicator
- 2.7. Aluminium anodised top rail
- 2.8. Aluminium Door Stopper Channel
- 2.9. Screws (SS Grade - 304) & Wall Plugs
- 2.10. Noise deafening tapes for grooves in doors & Pilasters.

#### **3. Quality**

- 3.1. Quality of the partition work shall be of GREENLAM or equivalent product

#### **4. Warranty:**

- 4.1. The quoted rate must be inclusive of ten (10) years of warranty for the partitions against any moisture/other defects and three (3) year warranty for the restroom workmanship and hardware (accessories) against any manufacturing defect.
- 4.2. The rate quoted shall be exclusive of GST and rate/amount of GST shall be shown in BoQ without any ambiguity.

Sd/-  
Director